



FETAKGOMO TUBATSE LOCAL MUNICIPALITY

15 April 2025

ADDENDUM ON THE ADVERTISED BID:

Tender description: Appointment of a service provider for electrification of Mountain Square

Bid number: FTM/T35/24/25

Notice is hereby given to all tenderers who have the intention to submit bid response for the above tender which was published on the municipal website and e-tender portal with the closing date of 29 April 2025.

Certain Provisional Sums amounts under **Section A – Preliminaries and General** were inadvertently omitted from the original Bill of Quantities (BOQ). Kindly find attached amended Bill of Quantities.

For any enquiries, please contact Mrs. LM Mohlala on 013 231 1000 or email Lmmohlala@ftlm.gov.za
Or the technical department , Mr. R.K Dikgale on rkdikgale@ftlm.gov.za or the engineer on victor@reliantconsulting.co.za

Kind regards

Mrs Magooa RM
Acting Municipal Manager

2025/04/15
Date

BILLS OF QUANTITIES ELECTRIFICATION OF PRAKTISEER MOUNTAIN SQUARE

[illegible]

[illegible]

F	MV Anchors	Unit	MQty	MRate	LQty	LRate	Mtotal	Ltotal	Total
1	1 Off conv anchor	e.a.	74		74				
2	1 Off flying stay	e.a.	9		9				
3	1 Off strut pole 12m	e.a.	21		21				
SUB-TOTAL									
G	LV Structures	Unit	MQty	MRate	LQty	LRate	Mtotal	Ltotal	Total
1	Int / susp (0-30 deg)	e.a.	333		333				
2	Intermediate service	e.a.	0		0				
3	Strain (0-60 deg)	e.a.	49		49				
4	Strain (60-90 deg)	e.a.	126		126				
5	Terminal	e.a.	122		122				
6	T-off from interm	e.a.	73		73				
7	T-off from strain	e.a.	0		0				
8	Cross int-int ass	e.a.	10		10				
9	ABC 3Ph Terminations at Tfr	e.a.	36		36				
SUB-TOTAL							749		
H	LV Anchors	Unit	MQty	MRate	LQty	LRate	Mtotal	Ltotal	Total
1	1 Off conv anchor	e.a.	408		408				
2	1 flying Stay	e.a.	10		10				
3	1 Off strut pole 9m	e.a.	60		60				
4	1 Off strut pole 11m		20		20				
SUB-TOTAL									
I	Service Boxes	Unit	MQty	MRate	LQty	LRate	Mtotal	Ltotal	Total
1A	6 Way Split Meter box : 1 x 50 A mcb	e.a.	410		410				
2B	5 - 8 Way Split Meter box : 2 x 63 A mcb	e.a.	0		0				
SUB-TOTAL									
J	Stringing	Unit	MQty	MRate	LQty	LRate	Mtotal	Ltotal	Total
1	Squirrel conductor	m	0		0				
2	Fox conductor	m	0		0				
3	Mink conductor	m	11454		11454				
4	35 mm sq ABC 1-ph	m	0		0				
5	35 mm sq ABC 2- ph	m	0		0				
6	35 mm sq ABC 3-ph	m	0		0				
7	70 mm sq ABC 1-ph	m	0		0				
8	70 mm sq ABC 2-ph	m	0		0				
9	70 mm sq ABC 3-ph	m	20639		20639				
10	MV miNK full tension joint	e.a.	20		20				
11	LV joint 35 mm full tension	e.a.	0		0				
12	LV joint 70 mm full tension	e.a.	50		50				
SUB-TOTAL									

[illegible]

M	Installation Earthing	Unit	MQty	MRate	LQty	LRate	Mtotal	Ltotal	Total
1	MV Earthing (Type 1 crowfoot)	e.a.	19		19				
2	LV Earthing (Type 1 crowfoot)	e.a.	38		38				
3	Bonding	e.a.	57		57				
SUB-TOTAL									
N	Pole Numbering	Unit	MQty	MRate	LQty	LRate	Mtotal	Ltotal	Total
1	MV pole number	e.a.	104		104				
2	LV pole number	e.a.	713		713				
SUB-TOTAL									
O	Commissioning	Unit	MQty	MRate	LQty	LRate	Mtotal	Ltotal	Total
1	Test & commission of Auto-Recloser Unit	e.a.	1		1				
2	Test & commission trsf and MV equipment	e.a.	19		19				
SUB-TOTAL									
P	Other Material & Auto Recloser	Unit	MQty	MRate	LQty	LRate	Mtotal	Ltotal	Total
1	Solid Sectional Links 3 Phase D-DT-1848	ea	7		7				
2	Fused Links 3 Phase D-DT-1849	ea	18		18				
3	Fused Links Dual Phase D-DT-1849	ea	0		0				
4	Sample line /Material Board	sum	8		8				
5	Live Work (Number of T-Offs)	ea	7		7				
6	Allow for Provisional amount for Supply & Installation Auto Recloser 22kV 400A 8KA complete with IRTU	Prov Sum	1	R 350 000,00	1	R 35 000,00	350 000,00	35 000,00	385 000,00
7	Modem Unit including Vodacom Start Pack and the necessary associated telecommunication cables, connectors and accessories to enable full functionality	sum	0		0				
8	Allow for Provisional amount for Supply & Installation of 22kV 200A 32 step closed delta Voltage Regulator and control box.	Prov Sum	0		0				
9	Upgrade existing MV line from Dual to 3 Phase	m	3000		3000				
10	Remove existing Transformer	m	0		0				
11	Dismantle existing MV line Including Removal of poles	m	0		1400				
12	Ant-climbing device	ea	57		57				
13	Tree felling (trunk diameter > 300mm)	ea	0		0				
SUB-TOTAL									
Q	House Connections	Unit	MQty	MRate	LQty	LRate	Mtotal	Ltotal	Total
1	Underground connection	ea	0		0				
2	Overhead connection	ea	1009		1009				
3	Supply ECU base, fixing rails and plug	ea	1009		1009				
4	Supply Din Rail Single Phase PLC Smart Split Meter with CIU 20A with Keypad (Meters to be Purchased from Eskom)	ea	1009		1009				
5	Interface : DC450 G3: PLC DC,230V (To be Purchased from Eskom)	ea	18		18				
6	KIOSK METER: 3PH,RAT/DC SECURE POLE MOUNT	ea	18		18				
7	Sealing of meters	ea	1009		1009				
8	COC Certificate ECA version	ea	1009		1009				
9	Supply and install additional 63A circuit breaker	ea	0		0				
10	Supply and install and wire 63A curve-2 cb to a split pp meter	ea	0		0				
11	Supply and mount readyboard	ea	1009		1009				
12	Capture and submit list of customers name and surname stand no meter no and contact no	ea	1009		1009				
SUB-TOTAL									

R	Supply ,Excavate and plant shack poles	Unit	MQty	MRate	LQty	LRate	Mtotal	Ltotal	Total
1A	5m Wood 120-140 mm tops	e.a.	404		404				
1B	Rock Drill	e.a.	0		0				
1C	Compressors	e.a.	0		0				
2	Compressors	e.a.	0		0				
3	Hand Excavate Cable trench -house connection	m	0		0				
4	Hand Excavate Cable trench-Road Crossing	m	0		0				
5	Install Cable Sleeves 110mm	m	0		0				
SUB-TOTAL									
S	LV Conductor (Supply Cable)	Unit	MQty	MRate	LQty	LRate	Mtotal	Ltotal	Total
1	4mm sq Airdac SNE plus Pilot wires	m	0		0				
2	6mm sq Airdac SNE plus Pilot wires	m	45405		45405				
SUB-TOTAL									